BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/05/2021-22 Date: 19.07.2021

Indent No: BBMP/2021-22/OW/WORK_INDENT47900

SCHEDULE -B

Name of Work: Construction of Gallery in JP Park ward no 17

Sl. No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	910.34	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	226.00	Rupees Two Hundred Twenty Six Only
2	90.80	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications,	Cum	2806.00	Rupees Two Thousand Eight Hundred Six Only
3	86.48	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6283.00	Rupees Six Thousand Two Hundred Eighty Three Only
4	1837.98	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications.	Sqm	413.00	Rupees Four Hundred Thirteen Only
5	446.51	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M20 for R.C.C works laid in 15 cms thick layers and well compacted by vibrating, curing, for foundations & sub-structure works with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) .	Cum	6700.00	Rupees Six Thousand Seven Hundred Only
6	44.65	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. TMT bars Fe 550	Tonne	90769.00	Rupees Ninety Thousand Seven Hundred Sixty Nine Only

For Sri Nanjundeshwara Construction

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

7	102.67	KSRB 2.6 : Providing and filling dust in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications. specification.	Cum	1319.43	Rupees One Thousand Three Hundred Nineteen And Paise Forty Three Only
8	6236.73	Fabrication supplying and erecting M.S. tubular trusses of all spans as per approved drawing & design with prefabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, letc., complete as per specification	Kgs	128.00	Rupees One Hundred Twenty Eight Only
9	671.60	TENSILE ROOFING	Sqm	11200.00	Rupees Eleven Thousand Two Hundred Only
10	82.80	Providing and laying pre-cast drain cover slab of 100mm thickness in CM1:3 including cost of all materials,labour,curing, transportation, loading, unloading etc.,as per doirections of the Enineer-in-charge. {Data Rate sheet enclosed}	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only

For Sri Nanjundeshwara Construction

Proprietor

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP